



Meter Station Interconnect — *Texas*

Project Overview

Evers & Sons Inc. provided full field installation services for a 700 MMcf meter station supporting an LNG export pipeline system in Texas. This project included site grading and stabilization, concrete, structural steel, mechanical piping and equipment installation, electrical and instrumentation, painting, and final site work. The facility supports accurate gas measurement and flow control critical to LNG export operations.

Key Equipment:

- Inlet vortex separator
- Gas measurement with flow control
- Gas chromatograph/analyzer
- 30 BBL closed drain tank
- Secondary containment

Scope of Work:

- Site grading & stabilization
- Concrete
- Secondary containment
- Structural steel
- Mechanical piping
- Mechanical equipment installation
- Electrical
- Instrumentation
- Facility painting
- Final site rock

Field Installation Statistics:

- ±30 cubic yards concrete
- ±3 tons structural steel
- 115 – prefabricated pipe spools
- ±1,000 linear ft. pipe – from 1" to 24"
- 95 welds
- ±3,200 field weld inches
- 96 flange torques

Company Overview

Evers & Sons Inc. is a third-generation, family-owned energy services company providing services across Engineering, Facilities, Fabrication, Pipeline, Maintenance, and Decommissioning & Asset Abandonment. Together, we connect engineering expertise with proven field execution to help our customers plan smarter, build efficiently, and operate with confidence.

Contact Information

contact@eversandsons.com

www.eversandsons.com

(979) 596-2139